


GENERAL SUMMARY

Prepared for: ILM Academy INC Learning Center 30 Mansell CT. Roswell GA 30076 Fulton County
 Project ID:
 Scope: G.C
 No. Of Floors: 1
 Date: 13-May-25



BUILDING GSF		14581	
DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	General Requirements	\$ 65,781	\$ 4.51
6000	Wood, Plastics & Composites	\$ 12,557	\$ 0.86
8000	Opening	\$ 84,980	\$ 5.83
9000	Finishes	\$ 275,840	\$ 18.92
10000	Specialties	\$ 5,743	\$ 0.39
11000	Equipments	\$ 3,330	\$ 0.23
12000	Furnishing	\$ 6,154	\$ 0.42
22000	Plumbing	\$ 111,985	\$ 8
23000	HVAC	\$ 91,553	\$ 6
26000	Electrical	\$ 129,204	\$ 9
27000	Communications	\$ 11,957	\$ 1
TOTAL TRADE COST		\$ 799,084	\$ 31
OVERHEAD AND PROFIT			
	21%	\$ 167,808	\$ 6.54
TAX			
	8%	\$ 37,869	\$ 2
SUGGESTED BID		\$ 1,004,761	\$ 40

DIVISION COST COMPARISON



General Requirements Wood, Plastics & Composites Opening Finishes Specialties Equipments Furnishing

COST BIDDING
 A Mark of Excellence

DETAILED BREAKDOWN OF ITEMS

Prepared for: ILM Academy INC Learning Center 30 Mansell CT, Roswell GA 30076 Fulton County
 Project ID:
 Scope: G.C



Date: 13-May-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST		
GENERAL REQUIREMENTS															
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 32,652.00	\$ 32,652.00		
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,855.00	\$ 4,855.00		
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 15,622.00	\$ 15,622.00		
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 12,652.00	\$ 12,652.00		
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
												SUBTOTAL	\$ 65,781		
WOOD & PLASTIC															
ROUGH CARPENTRY															
			BLOCKING												
8	A-120	A-120	2x4 Wooden Blocking	LF	180	10%	198	0.025	\$ 30.00	\$ 0.75	\$ 1.20	\$ 1.95	\$ 386		
			FINISH CARPENTRY												
			CABINETSRY & MILLWORK												
9			2'-0" Deep x 2'-10" High Base Cabinet	LF	34	10%	37	0.585	\$ 30.00	\$ 17.55	\$ 198.25	\$ 215.80	\$ 8,071		
10			2'-0" Deep x 1'-10" High Wall Cabinet	LF	28	10%	31	0.422	\$ 30.00	\$ 12.66	\$ 120.45	\$ 133.11	\$ 4,100		
												SUBTOTAL	\$ 12,557		
OPENINGS															
			HM DOOR & FRAME												
11	A130	Door Schedule /A130	D1: 3'-0" x 7'-0" x 1-3/4" Interior Wood Door W/ -Hollow Metal Frame	EA	33	0%	33	2.100	\$ 30.00	\$ 63.00	\$ 852.62	\$ 915.62	\$ 30,215		
12			D2: 3'-0" x 7'-0" x 1-3/4" Interior Wood Door W/ -Hollow Metal Frame (4'-6" x 7'-0") -1'-0" x7'-0" Glass Sidelight Vision Glazing	EA	3	0%	3	5.000	\$ 30.00	\$ 150.00	\$ 1,152.00	\$ 1,302.00	\$ 3,906		
13			D3: 3'-0" x 7'-0" x 1-3/4" Interior Wood Door W/ -Hollow Metal Frame (5'-6" x 7'-0") -2'-0" x7'-0" Glass Sidelight Vision Glazing	EA	1	0%	1	6.250	\$ 30.00	\$ 187.50	\$ 1,298.25	\$ 1,485.75	\$ 1,486		
14			D4: 3'-0" x 7'-0" x 1-3/4" Interior Wood Door W/ -Hollow Metal Frame -6"x27" Vision Lite	EA	2	0%	2	2.980	\$ 30.00	\$ 89.40	\$ 1,020.00	\$ 1,109.40	\$ 2,219		
15			D5: 6'-0" x 7'-0" Exterior Tempered Glass Pannel Door W/ -Aluminum Frame	EA	1	0%	1	5.850	\$ 30.00	\$ 175.50	\$ 1,898.40	\$ 2,073.90	\$ 2,074		
16			D6: 3'-0" x 7'-0" x 1-3/4" Interior Wood Door W/ -Hollow Metal Frame -1-HR Rated (60 Min) -1'-0" x7'-0" Glass Sidelight Vision Glazing	EA	1	0%	1	5.650	\$ 30.00	\$ 169.50	\$ 1,285.25	\$ 1,454.75	\$ 1,455		
			DOOR HARDWARE												
17			Typical Hardware Sets	EA	41	0%	41	1.600	\$ 30.00	\$ 48.00	\$ 325.20	\$ 373.20	\$ 15,301		
			Notes: Rated Door to Receive Closer -Control Access Door to Receive Panic Hardware -Hardware Levers and Locks to Be Schlage A1-Series -All Doors Hardware To Be ADA Required												
			DOOR TRIMS												
18			Door Trims	LF	1374	0%	1374	0.032	\$ 30.00	\$ 0.96	\$ 2.65	\$ 3.61	\$ 4,960		
			WINDOWS												
19					W1: 3'-0" x 7'-0" Tampered Glass Window W/ -Aluminum Frame	EA	22	0%	22	2.100	\$ 30.00	\$ 63.00	\$ 971.25	\$ 1,034.25	\$ 22,754
20					W2: 4'-0" x 3'-0" Crl Delux Sliding Service Glass Window W/ -Aluminum Frame -Unglazed Window Panel Notes: Window Shall Be White Commercial Storefront Insulated Glass in Aluminum Frames or Anderson Units ,Double Insulated Glas s, Corrosive Resistant Hardware and Insect Screens.	EA	1	0%	1	1.850	\$ 30.00	\$ 55.50	\$ 555.00	\$ 610.50	\$ 611
												SUBTOTAL	\$ 84,980		
FINISHES															
			DRY WALL												
21			Wall Type 1: 6" Metal Stud Framed Partition	LF	266	H	11								
22			5/8" Gypsum Wall Board - Each Side	SF	5284	10%	5812								
23			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	182	0%	182	0.305	\$ 30.00	\$ 9.15	\$ 15.20	\$ 24.35	\$ 4,432		
24			Drywall Finishes - Tapping, Mudding	EA	6	0%	6	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 175		
25			Tapping	LF	2656	10%	2922								
26			Mudding	LBs	280	10%	308								
27			Screws	EA	8736	0%	8736								
28			6" Metal Stud @ 16" O.C	LF	2107	10%	2318	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 6,537		
29			6" Metal Stud Bracing @ 24" O.C	LF	268	10%	294	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 830		
30			6" Top Metal Track	LF	266	10%	292	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 824		
31			6" Bottom Metal Track	LF	266	10%	292	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 824		
32			Acoustical Sealant	LF	1062	10%	1169	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 1,052		
33			Wall Type 1: 6" Metal Stud Framed Partition	LF	39	H	11								
34			5/8" Gypsum Wall Board	SF	407	10%	447								
35			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	14	0%	14	0.305	\$ 30.00	\$ 9.15	\$ 15.20	\$ 24.35	\$ 341		
36			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29		
37			Tapping	LF	208	10%	229								
38			Mudding	LBs	22	10%	24								
39			Screws	EA	672	0%	672								
40			5/8" Moisture Resistant Gypsum Wall Board	SF	407	10%	447								
41			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	14	0%	14	0.305	\$ 30.00	\$ 9.15	\$ 17.45	\$ 26.60	\$ 372		
42			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29		
43			Tapping	LF	208	10%	229								
44			Mudding	LBs	22	10%	24								
45			Screws	EA	672	0%	672								
46			6" Metal Stud @ 16" O.C	LF	316	10%	348	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 981		
47			6" Metal Stud Bracing @ 24" O.C	LF	41	10%	45	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 126		
48			6" Top Metal Track	LF	39	10%	43	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 120		
49			6" Bottom Metal Track	LF	39	10%	43	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 120		
50			Acoustical Sealant	LF	155	10%	170	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 153		

DETAILED BREAKDOWN OF ITEMS

Prepared for: ILM Academy INC Learning Center 30 Mansell CT. Roswell GA 30076 Fulton County
 Project ID:
 Scope: G.C



Date: 13-May-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
51	A-120-A130	Walls Details /A130	Wall Type 2: 3-5/8" Metal Stud Framed Partition	LF	40	H	11						
52			5/8" Gypsum Wall Board - Each Side	SF	848	10%	933						
53			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	30	0%	30	0.305	\$ 30.00	\$ 9.15	\$ 15.20	\$ 24.35	\$ 731
54			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
55			Tapping	LF	432	10%	475						
56			Mudding	LBs	45	10%	49						
57			Screws	EA	1440	0%	1440						
58			3-5/8" Metal Stud @ 16" O.C	LF	329	10%	362	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 822
59			3-5/8" Metal Stud Bracing @ 24" O.C	LF	42	10%	47	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 106
60			3-5/8" Top Metal Track	LF	40	10%	44	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 101
61			3-5/8" Bottom Metal Track	LF	40	10%	44	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 101
62			Acoustical Sealant	LF	162	10%	178	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 160
63			Wall Type 2: 3-5/8" Metal Stud Framed Partition	LF	71	H	10						
64			5/8" Moisture Resistant Gypsum Wall Board - Each Side	SF	1342	10%	1476						
65			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	47	0%	47	0.305	\$ 30.00	\$ 9.15	\$ 17.45	\$ 26.60	\$ 1,250
66			Drywall Finishes - Tapping, Mudding	EA	2	0%	2	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 58
67			Tapping	LF	672	10%	739						
68			Mudding	LBs	71	10%	78						
69			Screws	EA	2256	0%	2256						
70			3-5/8" Metal Stud @ 16" O.C	LF	514	10%	565	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 1,284
71			3-5/8" Metal Stud Bracing @ 24" O.C	LF	109	10%	120	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 272
72			3-5/8" Top Metal Track	LF	71	10%	78	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 176
73			3-5/8" Bottom Metal Track	LF	71	10%	78	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 176
74			Acoustical Sealant	LF	283	10%	311	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 280
75			Wall Type 2: 3-5/8" Metal Stud Framed Partition	LF	33	H	11						
76			5/8" Gypsum Wall Board-One Side	SF	342	10%	376						
77			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	12	0%	12	0.305	\$ 30.00	\$ 9.15	\$ 15.20	\$ 24.35	\$ 292
78			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
79			Tapping	LF	176	10%	194						
80			Mudding	LBs	18	10%	20						
81			Screws	EA	576	0%	576						
82			5/8" Moisture Resistant Gypsum Wall Board-Other Side	SF	342	10%	376						
83			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	12	0%	12	0.305	\$ 30.00	\$ 9.15	\$ 17.45	\$ 26.60	\$ 319
84			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
85			Tapping	LF	176	10%	194						
86			Mudding	LBs	18	10%	20						
87			Screws	EA	576	0%	576						
88			3-5/8" Metal Stud @ 16" O.C	LF	267	10%	294	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 668
89			3-5/8" Metal Stud Bracing @ 24" O.C	LF	35	10%	38	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 86
90			3-5/8" Top Metal Track	LF	33	10%	36	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 81
91			3-5/8" Bottom Metal Track	LF	33	10%	36	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 81
92			Acoustical Sealant	LF	130	10%	143	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 129
93			Wall Type 3A: 6" Metal Stud Framed Smoke Partition	LF	393	H	12						
94			5/8" Type 'X' Gypsum Wall Board - Each Side With Sound Acoustical Treatment	SF	8215	10%	9037						
95			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	283	0%	283	0.305	\$ 30.00	\$ 9.15	\$ 16.99	\$ 26.14	\$ 7,398
96			Drywall Finishes - Tapping, Mudding	EA	9	0%	9	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 262
97			Tapping	LF	4112	10%	4523						
98			Mudding	LBs	435	10%	479						
99			Screws	EA	13584	0%	13584						
100			6" Metal Stud @ 16" O.C	LF	3558	10%	3914	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 11,038
101			7/8" Resilient Furring Channel @ 24" O.C	LF	2358	10%	2594	0.022	\$ 30.00	\$ 0.66	\$ 0.85	\$ 1.51	\$ 3,917
102			6" Top Metal Track	LF	393	10%	432	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 1,219
103			6" Bottom Metal Track	LF	393	10%	432	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 1,219
104			Glass Fiber Insulation	LF	4717	10%	5188	0.012	\$ 30.00	\$ 0.36	\$ 1.20	\$ 1.56	\$ 8,094
105			Acoustical Sealant	LF	1572	10%	1729	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 1,557
106			Wall Type 3A: 6" Metal Stud Framed Smoke Partition	LF	13	H	12						
107			5/8" Type 'X' Gypsum Wall Board - Each Side With Sound Acoustical Treatment	SF	154	10%	169						
108			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	6	0%	6	0.305	\$ 30.00	\$ 9.15	\$ 16.99	\$ 26.14	\$ 157
109			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
110			Tapping	LF	80	10%	88						
111			Mudding	LBs	8	10%	9						
112			Screws	EA	288	0%	288						
113			5/8" Moisture Resistant Gypsum Wall Board-Other Side	SF	154	10%	169						
114			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	6	0%	6	0.305	\$ 30.00	\$ 9.15	\$ 17.45	\$ 26.60	\$ 160
115			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
116			Tapping	LF	80	10%	88						
117			Mudding	LBs	8	10%	9						
118			Screws	EA	288	0%	288						
119			6" Metal Stud @ 16" O.C	LF	128	10%	140	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 396
120			7/8" Resilient Furring Channel @ 24" O.C	LF	77	10%	85	0.022	\$ 30.00	\$ 0.66	\$ 0.85	\$ 1.51	\$ 128
121			6" Top Metal Track	LF	13	10%	14	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 40
122			6" Bottom Metal Track	LF	13	10%	14	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 40
123			Glass Fiber Insulation	LF	154	10%	169	0.012	\$ 30.00	\$ 0.36	\$ 1.20	\$ 1.56	\$ 264
124			Acoustical Sealant	LF	51	10%	56	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 51
125			Wall Type 3B: 3-5/8" Metal Stud Framed Smoke Partition	LF	23	H	12						
126			5/8" Type 'X' Gypsum Wall Board - Each Side With Sound Acoustical Treatment	SF	556	10%	612						
127			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	20	0%	20	0.305	\$ 30.00	\$ 9.15	\$ 16.99	\$ 26.14	\$ 523
128			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
129			Tapping	LF	288	10%	317						
130			Mudding	LBs	29	10%	32						
131			Screws	EA	960	0%	960						
132			3-5/8" Metal Stud @ 16" O.C	LF	221	10%	243	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 552
133			7/8" Resilient Furring Channel @ 24" O.C	LF	139	10%	153	0.022	\$ 30.00	\$ 0.66	\$ 0.85	\$ 1.51	\$ 231

DETAILED BREAKDOWN OF ITEMS

Prepared for: ILM Academy INC Learning Center 30 Mansell CT. Roswell GA 30076 Fulton County
Project ID:
Scope: G.C



Date: 13-May-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MAN/HR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
134			3-5/8" Top Metal Track	LF	23	10%	25	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 58
135			3-5/8" Bottom Metal Track	LF	23	10%	25	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 58
136			Glass Fiber Insulation	LF	278	10%	306	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 695
137			Acoustical Sealant	LF	93	10%	102	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 92
138			Wall Type 4: 3-5/8" Metal Stud Framed Smoke Partition	LF	62	H	11						
139			5/8" Gypsum Wall Board	SF	649	10%	714						
140			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	23	0%	23	0.305	\$ 30.00	\$ 9.15	\$ 15.20	\$ 24.35	\$ 560
141			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
142				Tapping	LF	336	10%	370					
143				Mudding	LBs	34	10%	38					
144				Screws	EA	1104	0%	1104					
145			3-5/8" Metal Stud @ 16" O.C	LF	499	10%	549	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 1,245
146			3-5/8" Metal Stud Bracing @ 24" O.C	LF	64	10%	70	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 151
147			3-5/8" Top Metal Track	LF	62	10%	68	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 154
148			3-5/8" Bottom Metal Track	LF	62	10%	68	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 154
149			Acoustical Sealant	LF	124	10%	136	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 122
150			Wall Type 4: 3-5/8" Metal Stud Framed Smoke Partition	LF	4	H	11						
151			5/8" Moisture Resistant Gypsum Wall Board	SF	41	10%	45						
152			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	2	0%	2	0.305	\$ 30.00	\$ 9.15	\$ 17.45	\$ 26.60	\$ 53
153			Drywall Finishes - Tapping, Mudding	EA	1	0%	1	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 29
154				Tapping	LF	32	10%	35					
155				Mudding	LBs	2	10%	2					
156				Screws	EA	96	0%	96					
157			3-5/8" Metal Stud @ 16" O.C	LF	41	10%	46	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 103
158			3-5/8" Metal Stud Bracing @ 24" O.C	LF	6	10%	7	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 15
159			3-5/8" Top Metal Track	LF	4	10%	4	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 10
160			3-5/8" Bottom Metal Track	LF	4	10%	4	0.025	\$ 30.00	\$ 0.75	\$ 1.52	\$ 2.27	\$ 10
161			Acoustical Sealant	LF	8	10%	9	0.015	\$ 30.00	\$ 0.45	\$ 0.45	\$ 0.90	\$ 8
162			Wall Type 5A: 6" Metal Stud Framed Smoke Partition	LF	59	H	12						
163			5/8" Type 'X' Gypsum Wall Board - Each Side With Sound Acoustical Treatment	SF	1425	10%	1567						
164			Drywall Hanging & Screws - Sheet Size: 4' x 8'	EA	49	0%	49	0.305	\$ 30.00	\$ 9.15	\$ 16.99	\$ 26.14	\$ 1,281
165			Drywall Finishes - Tapping, Mudding	EA	2	0%	2	0.388	\$ 30.00	\$ 11.64	\$ 17.50	\$ 29.14	\$ 58
166				Tapping	LF	720	10%	792					
167				Mudding	LBs	76	10%	83					
168				Screws	EA	2352	0%	2352					
169			6" Metal Stud @ 16" O.C	LF	548	10%	602	0.028	\$ 30.00	\$ 0.84	\$ 1.98	\$ 2.82	\$ 1,699
170			7/8" Resilient Furring Channel @ 24" O.C	LF	356	10%	392	0.022	\$ 30.00	\$ 0.66	\$ 0.85	\$ 1.51	\$

DETAILED BREAKDOWN OF ITEMS

Prepared for:	ILM Academy INC Learning Center 30 Mansell CT. Roswell GA 30076 Fulton County
Project ID:	
Scope:	G.C



Date: 13-May-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MAN/ HOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
189			Paint: Paint @ Metal Door Frames - 1 Coat of Primer - 2 Coat of Paint Note: Paint Details Are Missing On Plans. Please Verify Accordingly;	LF	1374	10%	1511	0.015	\$ 32.00	\$ 0.48	\$ 0.40	\$ 0.88	\$ 1,330
SUBTOTAL \$ 275,840													

SPECIALTIES

			BATH ACCESSORIES																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
--	--	--	------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

SUBTOTAL \$	5,743
-------------	-------

EQUIPMENT

			KITCHEN EQUIPMENT																
199	A-120	A-130	Refrigerator	EA	2	0%	2	2,650	\$ 30.00	\$ 79.50	\$ 1,320.25	\$ 1,399.75	\$ 2,800						
200			Microwave Oven	EA	1	0%	1	1,500	\$ 30.00	\$ 45.00	\$ 485.65	\$ 530.65	\$ 531						
			Note: Equipment Details Are Missing On Plans. Please Verify Accordingly.																
													SUBTOTAL \$ 3,330						

SUBTOTAL \$	3,330
-------------	-------

FURNISHING

			COUNTER TOP & BACK SPLASH											
201	A-120	A-120	COUNTERTOP											
			Countertop	SF	67	10%	74	0.350	\$ 30.00	\$ 10.50	\$ 69.00	\$ 79.50	\$ 5,859	
			BACKSPLASH											
202			4" H Backsplash	LF	34	10%	37	0.052	\$ 30.00	\$ 1.56	\$ 6.32	\$ 7.88	\$ 295	
			Note: Details Are Missing On Plans. Please Verify Accordingly.											

SUBTOTAL \$	6,154
-------------	-------

PLUMBING

[illegible]

DETAILED BREAKDOWN OF ITEMS														
Prepared for: ILM Academy INC Learning Center 30 Mansell CT. Roswell GA 30076 Fulton County														
Project ID:														
Scope: G.C														
												Date:	13-May-25	
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOURL	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
240	P101 & P102		2" / 1-1/2" Dia Waste Pipe Reducer	EA	4	0%	4	0.985	\$ 49.30	\$ 48.56	\$ 75.62	\$ 124.18	\$ 496.72	
241			3" / 1-1/4" Dia Waste Pipe Reducer	EA	3	0%	3	0.985	\$ 49.30	\$ 48.56	\$ 98.50	\$ 147.06	\$ 441.18	
242			3" / 2" Dia Waste Pipe Reducer	EA	2	0%	2	0.985	\$ 49.30	\$ 48.56	\$ 98.50	\$ 147.06	\$ 294.12	
243			4" / 1-1/4" Dia Waste Pipe Reducer	EA	1	0%	1	1.320	\$ 49.30	\$ 65.08	\$ 120.25	\$ 185.33	\$ 185.33	
244			4" / 3" Dia Waste Pipe Reducer	EA	4	0%	4	1.320	\$ 49.30	\$ 65.08	\$ 120.25	\$ 185.33	\$ 741.30	
				WASTE PIPE (ABOVE GRADE)										
				Cast Iron Pipe										
245				1-1/4" Dia Waste Pipe	LF	29	10%	31	0.140	\$ 49.30	\$ 6.90	\$ 14.50	\$ 21.40	\$ 673.78
246				1-1/2" Dia Waste Pipe	LF	17	10%	18	0.168	\$ 49.30	\$ 8.28	\$ 16.20	\$ 24.48	\$ 450.28
				WASTE PIPE FITTINGS										
				ELBOW										
247				1-1/4" Dia Waste Pipe 90 Deg Elbow	EA	9	0%	9	0.620	\$ 49.30	\$ 30.57	\$ 52.32	\$ 82.89	\$ 745.97
248				1-1/2" Dia Waste Pipe 45 Deg Elbow	EA	5	0%	5	0.620	\$ 49.30	\$ 30.57	\$ 52.32	\$ 82.89	\$ 414.43
249				1-1/4" Dia Waste Pipe 45 Deg Elbow	EA	9	0%	9	0.588	\$ 49.30	\$ 28.99	\$ 48.41	\$ 77.40	\$ 696.59
				WYE										
250				1-1/2" Dia Waste Pipe Wye	EA	5	0%	5	0.688	\$ 49.30	\$ 33.92	\$ 61.32	\$ 95.24	\$ 476.19
251				1-1/4" Dia Waste Pipe Wye	EA	9	0%	9	0.652	\$ 49.30	\$ 32.14	\$ 56.25	\$ 88.39	\$ 795.54
				VENT PIPE (ABOVE GRADE)										
				Cast Iron Pipe										
252				2" Dia Vent Pipe	LF	220	10%	242	0.240	\$ 49.30	\$ 11.83	\$ 15.98	\$ 27.81	\$ 6,741.52
253				3" Dia Vent Pipe	LF	237	10%	261	0.250	\$ 49.30	\$ 12.33	\$ 20.00	\$ 32.33	\$ 8,435.31
				VENT PIPE FITTINGS										
				ELBOW										
254				2" Dia Vent Pipe 90 Deg Elbow	EA	8	0%	8	0.752	\$ 49.30	\$ 37.07	\$ 65.32	\$ 102.39	\$ 819.15
255				3" Dia Vent Pipe 90 Deg Elbow	EA	12	0%	12	0.895	\$ 49.30	\$ 44.12	\$ 74.25	\$ 118.37	\$ 1,420.48
			TEE											
256			2" Dia Vent Pipe Tee	EA	3	0%	3	0.820	\$ 49.30	\$ 40.43	\$ 71.45	\$ 111.88	\$ 335.63	
257			3" Dia Vent Pipe Tee	EA	10	0%	10	0.985	\$ 49.30	\$ 48.56	\$ 98.50	\$ 147.06	\$ 1,470.61	
			REDUCER											
258			2" / 1-1/2" Dia Vent Pipe Reducer	EA	4	0%	4	0.820	\$ 49.30	\$ 40.43	\$ 71.45	\$ 111.88	\$ 447.50	
259			2" / 1-1/4" Dia Vent Pipe Reducer	EA	1	0%	1	0.820	\$ 49.30	\$ 40.43	\$ 71.45	\$ 111.88	\$ 111.88	
			PLUMBING FIXTURES											
260			1: Water Closet, ADA Accessible Fixture and Accessories. Notes: 2. MCGUIRE HEAVY LAVATORY SUPPLY STOP #H2165CCLK W/ Chrome Riser Tube (Typ. 2) or MCGUIRE HEAVY CLOSET SUPPLY STOP #H2166CCLK W/ Chrome Riser Tube. 3. Fixtures Shall Have The Maximum Flow Rates Of: Water Closet: 1.28 Gallon Per Flush, Lavatory: 0.5 Gallon Per Minute, Kitchen Sink: 2.0 Gallon Per Minute. 5. Final Connection by Plumbing Contractor.	EA	10	0%	10	2.200	\$ 49.30	\$ 108.46	\$ 535.90	\$ 644.36	\$ 6,443.60	
261			2: Lavatory, ADA Accessible Fixture and Accessories. Notes: 1. CRANE CAST BRASS P-Trap #JJ 8-5270 (Size As Required) P-Traps in Concealed Spaces May Be PVC. 2. MCGUIRE HEAVY LAVATORY SUPPLY STOP #H2165CCLK W/ Chrome Riser Tube (Typ. 2) or MCGUIRE HEAVY CLOSET SUPPLY STOP #H2166CCLK W/ Chrome Riser Tube. 3. Fixtures Shall Have The Maximum Flow Rates Of: Water Closet: 1.28 Gallon Per Flush, Lavatory: 0.5 Gallon Per Minute, Kitchen Sink: 2.0 Gallon Per Minute. 4. TRUEBRO LAV-GUARD, MODEL AS REQUIRED FOR P-TRAP And Angle Stops W/ Supplies Assemblies. 5. Final Connection by Plumbing Contractor.	EA	10									

Detailed Breakdown of Items															
Prepared for: ILM Academy INC Learning Center 30 Mansell CT. Roswell GA 30076 Fulton County Project ID: Scope:															
														Date:	13-May-25
SR #	Drawing #	Detail #	Description	Unit	Quantity	Wastage	Quantity w/ Wastage	Unit Manhour	Hourly Wage	Labor Cost	Mat. Cost	Unit Cost	Sub Cost		
278		Schedule Not Given	Recirculation Pump	EA	1	0%	1	1.850	\$ 49.30	\$ 91.21	\$ 298.25	\$ 389.46	\$ 389.46		
			MISCELLANEOUS												
			CLEANOUT & DRAINS												
279			4" Dia CO: Cleanout	EA	3	0%	3	0.985	\$ 49.30	\$ 48.56	\$ 132.25	\$ 180.81	\$ 542.43		
280			3" Dia FD: Floor Drain	EA	11	0%	11	0.752	\$ 49.30	\$ 37.07	\$ 102.65	\$ 139.72	\$ 1,536.96		
			VALVES												
281			1/2" Dia Ball Valve	EA	19	0%	19	0.298	\$ 49.30	\$ 14.69	\$ 11.25	\$ 25.94	\$ 492.89		
282			3/4" Dia Ball Valve	EA	10	0%	10	0.352	\$ 49.30	\$ 17.35	\$ 15.62	\$ 32.97	\$ 329.74		
			NO-HUB COUPLING												
283			1-1/4" Dia	EA	93	0%	93	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
284			1-1/2" Dia	EA	33	0%	33	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
285			2" Dia	EA	49	0%	49	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
286			3" Dia	EA	241	0%	241	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
287			4" Dia	EA	89	0%	89	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
			PIPE SUPPORT												
288			1/2" Dia Adjustable Clevis Hanger	EA	154	0%	154	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
289			3/4" Dia Adjustable Clevis Hanger	EA	14	0%	14	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
290			1-1/4" Dia Adjustable Clevis Hanger	EA	5	0%	5	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
291			1-1/2" Dia Adjustable Clevis Hanger	EA	4	0%	4	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
292			2" Dia Adjustable Clevis Hanger	EA	22	0%	22	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
293			3" Dia Adjustable Clevis Hanger	EA	24	0%	24	0.000	\$ -	\$ -	\$ -	\$ -	\$ -		
294			3/8" Dia Threaded Rod (1 Ea. = 1 FT)	EA	177	0%	177	0.100	\$ 49.30	\$ 4.93	\$ 2.65	\$ 7.58	\$ 1,341.66		
295			1/2" Dia Threaded Rod (1 Ea. = 1 FT)	EA	46	0%	46	0.120	\$ -	\$ -	\$ 3.20	\$ 3.20	\$ 147.20		
			TRENCHING & BACKFILLING												
296			Excavation & Backfilling (3' Deep x 1' Wide Trench) Including All Labor and Material/Equipment	CFT	1194	0%	1194	0.100	\$ 49.30	\$ 4.93	\$ -	\$ 4.93	\$ 5,886.42		
													SUBTOTAL \$	111,985	
HVAC															
297			FLEXIBLE DUCT												
298			6" Dia Flexible Duct	LF	63	10%	70	0.065	\$ 47.70	\$ 3.10	\$ 2.65	\$ 5.75	\$ 400.03		
299			8" Dia Flexible Duct	LF	522	10%	575	0.078	\$ 47.70	\$ 3.72	\$ 2.98	\$ 6.70	\$ 3,849.55		
			10" Dia Flexible Duct	LF	98	10%	107	0.095	\$ 47.70	\$ 4.53	\$ 3.53	\$ 8.06	\$ 865.48		
			AIR DEVICES												
300			C: Return Air Grille, TITUS PAR, Face Size: 12"x12", 50 CFM, Finish: White, 1 ea.	EA	8	0%	8	0.425	\$ 47.70	\$ 20.27	\$ 45.98	\$ 66.25	\$ 530.02		
301			D: Return Air Grille, TITUS PAR, Face Size: 24"x24", Finish: White, 1 ea.	EA	26	0%	26	0.620	\$ 47.70	\$ 29.57	\$ 102.98	\$ 132.55	\$ 3,446.40		
302			E: Supply Air Diffuser, TITUS PAS, Face Size: 24"x24", Neck Size: 6"	EA	2	0%	2	0.620	\$ 47.70	\$ 29.57	\$ 102.98	\$ 132.55	\$ 265.11		
303			E: Supply Air Diffuser, TITUS PAS, Face Size: 24"x24", Neck Size: 6"	EA	1	0%	1	0.620	\$ 47.70	\$ 29.57	\$ 102.98	\$ 132.55	\$ 132.55		
304			E: Supply Air Diffuser, TITUS PAS, Face Size: 24"x24", Neck Size: 6"	EA	6	0%	6	0.620	\$ 47.70	\$ 29.57	\$ 102.98	\$ 132.55	\$ 795.32		
305			F: Supply Air Diffuser, TITUS PAS, Face Size: 24"x24", Neck Size: 8"	EA	14	0%	1								

DETAILED BREAKDOWN OF ITEMS

Prepared for: ILM Academy INC Learning Center 30 Mansell CT, Roswell GA 30076 Fulton County
 Project ID:
 Scope: G.C



Date: 13-May-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
353			3/8" Threaded Rod	EA	182	0%	182	0.100	\$ 47.70	\$ 4.77	\$ 2.98	\$ 7.75	\$ 1,410.50
354			1" x 22 Ga. Strap	EA	91	0%	91	0.052	\$ 47.70	\$ 2.48	\$ 2.45	\$ 4.93	\$ 448.67
SUBTOTAL \$ 91,553													
ELECTRICAL													
DISTRIBUTION													
			CONDUIT										
355			1/2" Dia EMT Conduit	LF	84	10%	92	0.045	\$ 52.12	\$ 2.35	\$ 1.20	\$ 3.55	\$ 327.59
356			3/4" Dia EMT Conduit	LF	1262	10%	1389	0.052	\$ 52.12	\$ 2.71	\$ 1.65	\$ 4.36	\$ 6,054.23
357			1" Dia EMT Conduit	LF	37	10%	41	0.058	\$ 52.12	\$ 3.02	\$ 2.41	\$ 5.43	\$ 221.12
			CONDUCTOR										
358			#12 CU THHN/THWN	LF	252	10%	278	0.007	\$ 52.12	\$ 0.36	\$ 0.25	\$ 0.61	\$ 170.72
359			#10 CU THHN/THWN	LF	3351	10%	3884	0.008	\$ 52.12	\$ 0.42	\$ 0.29	\$ 0.71	\$ 2,746.05
360			#8 CU THHN/THWN	LF	269	10%	296	0.009	\$ 52.12	\$ 0.47	\$ 0.68	\$ 1.15	\$ 340.51
361			#6 CU THHN/THWN	LF	961	10%	1057	0.010	\$ 52.12	\$ 0.52	\$ 0.88	\$ 1.40	\$ 1,480.96
362			#4 CU THHN/THWN	LF	73	10%	80	0.012	\$ 52.12	\$ 0.63	\$ 1.45	\$ 2.08	\$ 166.61
			LUGS										
363			Compression Lug CU With 1-Hole, #8 CU Wire	EA	6	0%	6	0.152	\$ 52.12	\$ 7.92	\$ 2.65	\$ 10.57	\$ 63.43
364			Heat Shrink Tubing for #8 CU Wire	EA	6	0%	6	0.050	\$ 52.12	\$ 2.61	\$ 0.85	\$ 3.46	\$ 20.74
365			Compression Lug CU With 1-Hole, #6 CU Wire	EA	28	0%	28	0.192	\$ 52.12	\$ 10.01	\$ 3.25	\$ 13.26	\$ 371.20
366			Heat Shrink Tubing for #6 CU Wire	EA	28	0%	28	0.065	\$ 52.12	\$ 3.39	\$ 0.98	\$ 4.37	\$ 122.30
367			Compression Lug CU With 1-Hole, #4 CU Wire	EA	4	0%	4	0.210	\$ 52.12	\$ 10.95	\$ 3.98	\$ 14.93	\$ 59.70
368			Heat Shrink Tubing for #4 CU Wire	EA	4	0%	4	0.100	\$ 52.12	\$ 5.21	\$ 1.20	\$ 6.41	\$ 25.65
			CIRCUIT BREAKER										
369			1P/20A Breaker	EA	55	0%	55	0.252	\$ 52.12	\$ 13.13	\$ 21.25	\$ 34.38	\$ 1,891.13
370			1P/40A Breaker	EA	1	0%	1	0.320	\$ 52.12	\$ 16.68	\$ 38.65	\$ 55.33	\$ 55.33
371			1P/50A Breaker	EA	8	0%	8	0.388	\$ 52.12	\$ 20.22	\$ 42.25	\$ 62.47	\$ 499.78
372			1P/60A Breaker	EA	1	0%	1	0.452	\$ 52.12	\$ 23.56	\$ 49.50	\$ 73.06	\$ 73.06
373			3P/20A Breaker	EA	2	0%	2	0.420	\$ 52.12	\$ 21.89	\$ 49.20	\$ 71.09	\$ 142.18
374			3P/30A Breaker	EA	4	0%	4	0.452	\$ 52.12	\$ 23.56	\$ 68.32	\$ 91.88	\$ 367.51
			PANEL										
375			Panel HVAC-1: 400A, 120/208V, 3Ph, 4W, Mains: MLO, 65KAIC, 84	EA	1	0%	1	8.000	\$ 52.12	\$ 416.96	\$ 4,266.60	\$ 4,683.56	\$ 4,683.56
376			Panel L-1: 150A, 120/208V, 3Ph, 4W, Mains: MLO, 10KAIC, 42	EA	1	0%	1	3.650	\$ 52.12	\$ 190.24	\$ 1,093.89	\$ 1,284.13	\$ 1,284.13
377			Panel L-1 (2): 100A, 120/208V, 3Ph, 4W, Mains: MLO, 10KAIC, 42	EA	1	0%	1	3.100	\$ 52.12	\$ 161.57	\$ 785.62	\$ 947.19	\$ 947.19
			DEVICES										
378			1200A Utility Revenue Meter	EA	1	0%	1	8.000	\$ 52.12	\$ 416.96	\$ 8,497.25	\$ 8,914.21	\$ 8,914.21
			DISCONNECT SWITCH										
379			1P/20A Non Fused Disconnect Switch, SQAURE D	EA	1	0%	1	0.520	\$ 52.12	\$ 27.10	\$ 65.98	\$ 93.08	\$ 93.08
380			1P/20A Non Fused Disconnect Switch, SQAURE D	EA	1	0%	1	0.520	\$ 52.12	\$ 27.10	\$ 65.98	\$ 93.08	\$ 93.08
381			1P/40A Non Fused Disconnect Switch, SQAURE D	EA	1	0%	1	0.660	\$ 52.12	\$ 31.27	\$ 79.20	\$ 110.47	\$ 110.47
382			1P/50A Non Fused Disconnect Switch, SQAURE D	EA	7	0%	7	0.752	\$ 52.12	\$ 39.19	\$ 86.92	\$ 126.11	\$ 882.80
383			1P/60A Non Fused Disconnect Switch, SQAURE D	EA	1	0%	1	0.788	\$ 52.12	\$ 41.07	\$ 98.00	\$ 139.07	\$ 139.07
384			3P/20A Non Fused Disconnect Switch, SQAURE D	EA	1	0%	1	0.620	\$ 52.12	\$ 32.31	\$ 132.20	\$ 164.51	\$ 164.51
385			3P/30A Non Fused Disconnect Switch, SQAURE D	EA	3	0%	3	0.698	\$ 52.12	\$ 36.38	\$ 152.20	\$ 188.58	\$ 565.74
386			3P/30A Non Fused Motor Rated Disconnect Switch, SQAURE D	EA	1	0%	1	0.788	\$ 52.12	\$ 41.07	\$ 165.98	\$ 207.05	\$ 207.05
			POWER										
			CONDUIT										
387			1/2" EMT Conduit	LF	3821	10%	4203	0.045	\$ 52.12	\$ 2.35	\$ 1.20	\$ 3.55	\$ 14,901.67
388			3/4" PVC SCH 40 Conduit	LF	50	10%	55	0.062	\$ 52.12	\$ 3.23	\$ 0.96	\$ 4.19	\$ 230.53
			CONDUCTOR										
389			#12 CU THHN/THWN	LF	9672	10%	10639	0.007	\$ 52.12	\$ 0.36	\$ 0.25	\$ 0.61	\$ 6,541.49
390			#10 CU THHN/THWN	LF	1956	10%	2152	0.008	\$ 52.12	\$ 0.42	\$ 0.29	\$ 0.71	\$ 1,521.10
			DEVICE										
391			Duplex Receptacle	EA	111	0%	111	0.251	\$ 52.12	\$ 13.08	\$ 19.25	\$ 32.33	\$ 3,588.87
392			Countertop Duplex Receptacle, GFI	EA	10	0%	10	0.320	\$ 52.12	\$ 16.68	\$ 32.68	\$ 49.36	\$ 493.58
393			Round Floor Box Mounted Duplex Receptacle	EA	3	0%	3	0.452	\$ 52.12	\$ 23.56	\$ 452.20	\$ 475.76	\$ 1,427.27
394			Countertop Duplex Receptacle	EA	6	0%	6	0.420	\$ 52.12	\$ 21.89	\$ 32.65	\$ 54.54	\$ 327.24
395			Single Pole Switch	EA	3	0%	3	0.252	\$ 52.12	\$ 13.13	\$ 5.32	\$ 18.45	\$ 55.36
396			Motor Rated Switch	EA	2	0%	2	0.620	\$ 52.12	\$ 32.31	\$ 85.62	\$ 117.93	\$ 235.87
			LIGHTING										
			CONDUIT										
397			3/4" EMT Conduit	LF	2335	10%	2569	0.052	\$ 52.12	\$ 2.71	\$ 1.65	\$ 4.36	\$ 11,200.24
			CONDUCTOR										
398			#12 CU THHN/THWN	LF	1724	10%	1897	0.007	\$ 52.12	\$ 0.36	\$ 0.25	\$ 0.61	\$ 1,166.05
399			#10 CU THHN/THWN	LF	353	10%	388	0.008	\$ 52.12	\$ 0.42	\$ 0.29	\$ 0.71	\$ 274.40
400			#8 CU THHN/THWN	LF	4929	10%	5421	0.009	\$ 52.12	\$ 0.47	\$ 0.68	\$ 1.15	\$ 6,229.56
			LIGHTING FIXTURES										
401			A: 2x4 Surface Mounted, LITHONIA OR APPROVED EQUAL Mounting: Surface Watts: 50W	EA	148	0%	148	0.820	\$ 52.12	\$ 42.74	\$ 128.65	\$ 171.39	\$ 25,365.48
402			AE: 2x4 LED Lighting Fixture With Emergency Battery Backup, LITHONIA OR APPROVED EQUAL Mounting: Surface Watts: 50W	EA	29	0%	29	0.992	\$ 52.12	\$ 51.70	\$ 162.00	\$ 213.70	\$ 6,197.39
403			B: 2x2 Surface Mounted, LITHONIA OR APPROVED EQUAL Mounting: Surface Watts: 30W	EA	16	0%	16	0.750	\$ 52.12	\$ 39.09	\$ 89.25	\$ 128.34	\$ 2,053.44
404			BE: Same As A With Emergency Battery Backup, LITHONIA OR APPROVED EQUAL Mounting: Surface Watts: 30W	EA	13	0%	13	0.882	\$ 52.12	\$ 45.97	\$ 132.25	\$ 178.22	\$ 2,316.86
405			C: Led Low Bay Lights. Provide Necessary Accessories For Mounting From Ceiling Structure, LITHONIA OR APPROVED EQUAL Mounting: Pendant Watts: 82W	EA	11	0%	11	1.250	\$ 52.12	\$ 65.15	\$ 305.98	\$ 371.13	\$ 4,082.43
406			CE: Same As A With Emergency Battery Backup, LITHONIA OR APPROVED EQUAL Mounting: Pendant Watts: 82W	EA	5	0%	5	1.500	\$ 52.12	\$ 78.18	\$ 388.65	\$ 466.83	\$ 2,334.15
407			EM: Emergency Light With Battery Back Up, LITHONIA OR APPROVED EQUAL Mounting: Wall	EA	1	0%	1	0.895	\$ 52.12	\$ 46.65	\$ 85.62	\$ 132.27	\$ 132.27
408			R: 6" Aperture Led Down Lights, GOTHAM OR APPROVED EQUAL Mounting: Recessed Watts: 20W	EA	2	0%	2	0.980	\$ 52.12	\$ 51.08	\$ 247.85	\$ 298.93	\$ 597.86
409			RE: Same As A With Emergency Battery Backup, GOTHAM OR APPROVED EQUAL Mounting: Recessed Watts: 20W	EA	2	0%	2	1.020	\$ 52.12	\$ 53.16	\$ 320.25	\$ 373.41	\$ 746.82

DETAILED BREAKDOWN OF ITEMS

Prepared for: ILM Academy INC Learning Center 30 Mansell CT, Roswell GA 30076 Fulton County
 Project ID:
 Scope: G.C



Date: 13-May-25

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
410			X: Exit Sign With Battery Back Up Single Face Or Double Face Exit Sign Shall BE Mounted AS Indicated On The Drawing Directional Arrows As Indicated In The Drawing, LITHONIA OR APPROVED EQUAL Mounting: Wall Or Ceiling Mounted	EA	4	0%	4	0.855	\$ 52.12	\$ 44.56	\$ 120.65	\$ 165.21	\$ 660.85
			LIGHTING CONTROL										
411			Single Pole Switch	EA	13	0%	13	0.185	\$ 52.12	\$ 9.64	\$ 4.85	\$ 14.49	\$ 188.40
412			Single Pole Occupancy Sensor With Vacant Dimmer Switch, Wall Mo	EA	23	0%	23	0.488	\$ 52.12	\$ 25.43	\$ 71.48	\$ 96.91	\$ 2,229.03
413			Three Way Switch	EA	11	0%	11	0.298	\$ 52.12	\$ 15.53	\$ 21.98	\$ 37.51	\$ 412.63
414			Four Way Switch	EA	1	0%	1	0.320	\$ 52.12	\$ 16.68	\$ 32.50	\$ 49.18	\$ 49.18
			MISCELLANEOUS										
415			Junction Box	EA	3	0%	3	0.210	\$ 52.20	\$ 10.96	\$ 4.25	\$ 15.21	\$ 45.64
			SAW CUT										
416			Saw Cut & Repair Concrete Floor For Conduit Installation	LF	50	0%	50	0.120	\$ 52.20	\$ 6.26	\$ -	\$ 6.26	\$ 313.20
												SUBTOTAL	\$ 129,204

COMMUNICATION													
TELECOMMUNICATION													
			CONDUIT										
417			3/4" EMT Conduit Upto Ceiling	LF	540	10%	594	0.052	\$ 52.12	\$ 2.71	\$ 1.65	\$ 4.36	\$ 2,589.98
418			3/4" PVC SCH 40 Conduit	LF	50	10%	55	0.062	\$ 52.12	\$ 3.23	\$ 0.96	\$ 4.19	\$ 230.53
			CONDUCTOR										
419			CAT6 Cable	LF	6740	10%	7414	0.006	\$ 52.12	\$ 0.31	\$ 0.45	\$ 0.76	\$ 5,654.81
			J Hooks										
420			2" J Hooks	EA	91	0%	91	0.100	\$ 52.12	\$ 5.21	\$ 2.15	\$ 7.36	\$ 669.94
			DEVICES										
421			Combination Telephone And Data Outlet	EA	33	0%	33	0.210	\$ 52.12	\$ 10.95	\$ 21.25	\$ 32.20	\$ 1,062.44
422			Round Floor Mounted Box Combination Telephone And Data Outlet	EA	3	0%	3	0.452	\$ 52.12	\$ 23.56	\$ 168.00	\$ 191.56	\$ 574.67
			Back Box	EA	36	0%	36	0.100	\$ 52.20	\$ 5.22	\$ 4.25	\$ 9.47	\$ 340.92
			Faceplate	EA	36	0%	36	0.085	\$ 52.20	\$ 4.44	\$ 2.98	\$ 7.42	\$ 267.01
			RJ45 Connector	EA	72	0%	72	0.100	\$ 52.20	\$ 5.22	\$ 2.65	\$ 7.87	\$ 566.64
												SUBTOTAL	\$ 11,957

												PROJECTED COST	\$799,084
OVERHEAD AND PROFIT												21%	\$167,808
TAX												8%	\$37,869
SUGGESTED BID													\$1,004,761

Notes:
 1. Online sources are used for pricing.
 2. Prices can vary depending upon field conditions.

