COST BIDDING
A Mark of Excellence

Arrangements Have Been Made, Terms Will Be As Follows:

50% Deposit Due Before Materials Will Be Ordered. Balance Will Be Due At Time Of Final Payout.

We Accept Person or Company Checks, Visa, Mastercard and American Express

		DIVISION 09 - FINISHES			

QTY	UNIT	ITEM	DESCRIPTION	UNIT PRICE	LINE TOTAL
			FLOORING		
1092	SQ FT	**Tag SLC-1: Sealed Concrete**	**Manufacturer:** TBD **Product:** Sealant Coat **Color:** TBD	$ -	$ -
3135	SQ FT	**TAG SLC-2: Polished Concrete**	**Manufacturer:** TBD **Product:** Colored Polished Concrete **Color:** TBD	$ -	$ -
1552	SQ FT	**Tag LVT-1: Luxury Vinyl Tile**	**Manufacturer:** J+J **Product:** Timeless **Color:** Curio 1007 **Size:** 9"x48" **Pattern:** 1/3 Drop Install Pattern	$ -	$ -
112	SQ FT	**Tag CT-1: Porcelain Floor Tile**	**Manufacturer:** Daltile **Product:** Volume 1.0 **Color:** Truffle **Size:** 12"x12"	$ -	$ -
			WALL BASE		
39	FT	**Tag CT-1: Porcelain Tile Wall Base**	**Manufacturer:** Daltile **Product:** Volume 1.0 **Color:** Truffle **Size:** 6"H **Note:** In Case Of Discrepancies, Wall Base Type As Shown In Elevations Shall Govern Over The Schedule.	$ -	$ -
878	FT	**Tag RB-1: Rubber Vinyl Wall Base**	**Manufacturer:** Johnsonite **Product:** Traditional Vinyl 1/8" Base **Color:** Brown 47 **Size:** 4"H	$ -	$ -
			WALL TILE		
139	SQ FT	**Tag CT-2: Ceramic Wall Tile**	**Manufacturer:** Daltile **Product:** Mythology Rectangle Undulated **Color:** Santorini **Size:** 4"x12"	$ -	$ -
			TRANSITION STRIP		
23	FT	**Rubber Transition Strip (Sealed Concrete To LVT)**	**Manufacturer:** TBD **Model:** TBD **Color:** TBD **Size:** TBD	$ -	$ -
6	FT	**Metal Edge Trim Transition Strip (LVT To Porcelain Floor Tile)**	**Manufacturer:** TBD **Model:** TBD **Color:** TBD **Size:** TBD	$ -	$ -

50% Deposit Required	Sub-Total:	$ -
This Quote Is Based On The Provided Plans Along With The Specifications On The Finish Schedule	Tax:	$ -
Unless Otherwise Stated Above, This Bid Does Not Include Demolition, Floor Prep. Or Floor Levelling & Repairs, Any Required Floor Prep., Levelling Or Repairs Will Be Billed On A Time & Material Basis.	Total:	$ -
Any Additions Or Changes Will Be Detailed On A Change Order Which Will Need To Be Approved		
And Signed Before Commencement Of The Work		