



Date: 03/19/25

\$1,233,142

MATERIAL LIST

Prepared for: Loyola Fieldhouse Roof Replacement - 1230 W Greenleaf Ave, Chicago, IL 60626
 Project ID: 03172025
 Scope: Roofing



2-Jun-25

SR #	DESCRIPTION	UNIT	QUANTITY	SUB COST
THERMAL & MOISTURE PROTECTION				
ROOFING				
	WATERPROOFING:			
	Seka Saranfil or J & M 80 MI PVC 20-year warranty roof	SF	31663	
1	SarnaFil G410 80 mil 10' x 100' - Reflective Gray	ROLL	36	\$ -
2	Sarnacol 2170 solvent adhesive (5 gals) -5 Gallon Pail Coverage: 400 SF	PAIL	89	\$ -
3	SarnaFil Dens-Deck Prime 1/2" x 4 x 4 (50 pcs/pallet)	PALLET	40	\$ -
4	Sarnacol AD Board Adhesive Part A (15 gals) -80 SF Per Gallon Coverage	DRUM	26	\$ -
5	Sarnacol AD Board Adhesive Part B (15 gal.) -80 SF Per Gallon Coverage	DRUM	26	\$ -
6	Vapor Retarder Primer SB (5 gals) -400 SF Per Gallon Coverage	PAIL	16	\$ -
7	Vapor Retarder SA 31 3.74x133.8 ft	ROLL	63	\$ -
8	SarnaStop (10 LF; 25 Each/Tube)	TUBE	5	\$ -
INSULATION				
9	R-30 Insulation Board (8'-0"x4'-0")	EA	989	\$ -
EAVE				
10	Drip Edge Flashing (10 LF)	EA	52	\$ -
PARAPET WALL				
Parapet Wall				
11	Counter Flashing (10 LF)	EA	135	\$ -
12	Metal Coping (10 LF)	EA	135	\$ -
13	Cant Strip (10 LF)	EA	135	\$ -
PENETRATIONS				
14	Penetrations Installations Perimeter (137 LF)	EA	25	\$ -
ROOF HATCH				
15	Install a new lockable hatch	EA	1	\$ -
ROOF DRAIN				
16	Roof Drains Installation (Detail Not Provided & Assumed)	EA	8	\$ -
ROOF ACCESSORIES				
17	XPN Plates -Note: 1 Pail = 500 Pieces	PAIL	18	\$ -
18	1-1/2" Long Masonry Anchor For Securing Roofing System To Masonry Substrates. -Note: 1 Box = 1000 Pieces	BOX	1	
19	12" Wide x 10' Long Detail Membrane, Reflective Gray -Note: 1 Box = 20 Pieces	BOX	7	
20	DS100 Flashing Rolls 12" x 75' Long	Rolls	20	\$ -
21	Sarnacol 2175 Bonding Adhesive For Flashing -Note: 1 Canister Covers 400 SF	CANISTER	4	
				\$